

APPENDIX A- Etheridge Shire Council Cyclone Imogen

Treatment codes	Treatments
T1	Asphalt surfacing, <50mm thickness
T2	Bitumen spray seal, 2-coat
T3	Bulk excavate surplus material and remove from site
T4	Bulk excavate surplus material to spoil
T5	Bulk fill - imported
T6	Bulk fill - local
T7	Clear mixed debris and remove from site
T8	Desilt drainage structure - removal of silt and debris
T9	Foamed bitumen stabilisation - including 50mm corrector. Excludes seal
T10	Gravel Resheeting 100mm
T11	Gravel Resheeting 150mm
T12	Gravel/material supply
T13	Heavy formation grading
T14	Heavy formation grading incorporating 75mm of imported material
T15	Heavy shoulder grading - incorporating 50mm of imported material
T16	In-situ stabilisation - including 50mm corrector. Excludes seal
T17	Light formation grading
T18	Medium formation grading
T19	Other - provide details of treatment within 'Damage description' field
T20	Patch repair - patch local unbound pavement failure (<20m ²). Includes 2 coat bitumen seal
T21	Pothole repair <1m ²
T22	Reconstruct reinforced concrete
T23	Reconstruct unbound granular base. Excludes seal
T24	Reconstruct unbound granular pavement. Excludes seal
T25	Reconstruct unsealed shoulder - repair isolated shoulder failure (<20m ²)
T26	Repair drainage structure - excavate, repair and reinstate
T27	Repair road signage
T28	Repair stone pitching
T29	Repair with flowable concrete
T30	Replace concrete pipe <600mm dia.
T31	Replace concrete pipe <900mm dia.
T32	Replace concrete pipe >1200mm dia.
T33	Replace guide posts or markers
T34	Replace head/end wall <375mm pipe or RCBC
T35	Replace head/end wall <600mm pipe or RCBC
T36	Replace head/end wall <900mm pipe or RCBC
T37	Replace sign (complete) - standard road sign, includes post
T38	Reshape table drain (1 side)
T39	Rock protection
T40	Heavy formation grading incorporating 50mm of imported material