

Contract No **ESC2024_024**

Description **Replacement of security fencing in Einasleigh Air strip**

Tenderer

Please Note: Cells shaded in green must be completed, all other cells are locked for editing

Item	Description of Work	Est Qty	Unit	Rate (\$) (GST Ex)	Amount (\$) (GST Ex)
A	Replacement of security fencing in Einasleigh Air strip				\$ -
TOTAL CONTRACT AMOUNT					\$ -

*This schedule is NOT a Bill of Quantities but it may be used during the contract period to supplement other forms of assessing the value of the Works completed for payment purposes.
 The Tenderer hereby acknowledges and agrees that the Principal does not guarantee or warrant the accuracy or completeness of the information provided in this Schedule and declares that the Tenderer has not relied on this information in the preparation of its Tender.
 The Tenderer further acknowledges and agrees that the Tenderer is responsible for taking out its own quantities and determining the actual quantities of the work required. The Tenderer hereby releases the Principal now and forever any liability whatsoever as a result of or arising from the supply of this information.*

Item No	Description of Work	Est Qty	Unit	Rate (\$) (GST Ex)	Amount (\$) (GST Ex)
	All works are to be performed in accordance with Etheridge Shire council Specification for security fencing unless otherwise specified. All works priced in this bill of quantities must be inclusive of business overheads, profit, site establishment, management of quality assurance systems, traffic control, environmental management and oh&s management.				
	SITE PREPARATION				
	Site Establishment, Site Management, Set Out of Works, Environmental Management & Protection of Works				
1.	Site establishment and setting out of the Works as specified	1	Item		
	Demolition and dumping				
2	Existing concrete and fencing	1	Item		
	Excavation works				
3	Excavaton works	73	m ³		
	Supply and pour 32Mpa concrete				
4	Supply and pour 32 Mpa concrete with associated works	73	m ³		
	Supply and install of 80 mm NB Medium galvanised pipe post at 2600 mm capped for corners				
5	Supply and install of 80 mm NB Medium galvanised pipe post at 2600 mm capped for corners	11	Nos.		
	Gate posts				
6	Supply and install of 80 mm NB Medium galvanised pipe post at 2600 mm capped for gate posts	8	Nos.		
	Supply and install of 50 mm NB Medium galvanised pipe post at 2600 mm capped for strainer posts				
7	Supply and install of 50 mm NB Medium galvanised pipe post at 2600 mm capped for strainer posts	22	Nos.		
	Supply and install of 50 mm NB Medium galvanised pipe post at 2600 mm capped for intermediate posts				
8	Supply and install of 50 mm NB Medium galvanised pipe post at 2600 mm capped for intermediate posts	1253	Nos.		
	Supply and install of 1800 mm high black PVC chain wire mesh signle gate at 1 m open size				
9	Supply and install of 1800 mm high black PVC chain wire mesh double gate at 6 m open size	2	Nos.		
	Supply and install of 1800 mm x 50 mm x 2.5 mm black PVC chain wire mesh				
10	Supply and install of 1800 mm x 50 mm x 2.5 mm black PVC chain wire mesh	3278	m		
	Supply and install of Fauna mesh of 900 mm x 50 mm x 1.4 mm HDG hexagonal mesh, pegged to the ground at 1 meter centres				
11	Supply and install of Fauna mesh of 900 mm x 50 mm x 1.4 mm HDG hexagonal mesh, pegged to the ground at 1 meter centres	3252	m		
	Supply and install of 32 mm NB galvanised double bent stays at 3250 mm post post				
12	Supply and install of 32 mm NB galvanised double bent stays at 3250 mm post post	22	No.		
	REINSTATEMENT WORKS and Demobilisation				
13	Final clean up, removal of all temporary structures and reinstatement to all disturbed areas to equal or better than pre-existing conditions. Disturbed nature strip to be sown and fertilised with Council approved grass seed mixture.	1	Item		
TOTAL LUMP SUM AMOUNT for ITEM A					