

Item	Description	Quantity	Unit	Supplied by Subcontractor
1	50mm PVC pipe for headwall weepholes	3	m	
2	Megaflo 170 x 40mm	50	m	
3	2400 x 300 x 20 compressible filler (Jaybro's Bitumen Board Expansion Joint or equivalent)	1	ea	Y
4	Bunnings' Bondall 4L BondCrete Cement Additive or equivalent	1	ea	Y
5	1:3 cement mortar for 1800 x 1800 SLBC	0.2	m3	Y
6	19 x 19 chamfer (supplied by Etheridge Shire Council)			
7	60mm and 75mm cover aspro (supplied by ARC)			
8	R16 x 800 galvanised dowel with 300 sleeve (supplied by ARC)			
9	10m x 150mm Denso tape	8	roll	Y
10	Bitumen coating (Bunnings' Crommelin 4L Blackseal Heavy Duty Bitumen Waterproofing Membrane or equivalent)	1	ea	Y
11	Curing agent (Fosroc Concure A99 20L or equivalent)	1	ea	Y
12	Formwork & accessories			Y
13	Standard tools and small plant for FRP (Formwork reinforcement pour)			Y