



REQUEST FOR QUOTATION

2025 DRFA RESTORATION WORKS - GEORGETOWN CEMETERY
FENCING

CONTRACT NO: ESC2026-011-Q

Request for Quotation

PART 1 – PREAMBLE

Etheridge Shire Council invites Quotations from suitably qualified respondents for the DRFA reconstruction of Georgetown cemetery fencing.

As described in more detail in Part 5 – Scope.

Practical Completion to be no later than 30th of October, 2026.

PART 2 – GENERAL INFORMATION

1. Contract details:	2025 DRFA Restoration Works – Georgetown Cemetery Fencing Contract No. : ESC2026-011-Q	
2. Communications by Respondents:	Communications regarding the Procurement Process must be submitted to www.vendorpanel.com.au no later than 3 calendar days prior to the time stated in Item 3 (as extended if at all, pursuant to the Procurement Process Conditions).	
3. Submission of Quotation:	Responses must be submitted to tender@etheridge.qld.gov.au by no later than 12pm on Wednesday the 8 th of April 2026. <i>Note// Adequate time must be allowed for the Quotation and all supporting documents to be uploaded or received by this time.</i>	
4. Evaluation Criteria:	Evaluation Criteria	Weighting (%) (Optional)
	Price	80%
	Program	20%
5. Quotation to be valid for:	90 calendar days after the time stated in Item 3 (as extended if at all, pursuant to the Procurement Process Conditions)	
6. Complaints:	Complaints regarding Procurement Process to be directed to: Alan Clark at AlanC@etheridge.qld.gov.au	

PART 3 – PROCUREMENT PROCESS CONDITIONS

The Procurement Process is governed by, and this Request for Quotation is to be read in conjunction with, the Procurement Process Conditions attached to or provided with this Request for Quotation and identified as ESC2026-011-Q - Procurement Process Conditions.

PART 4 – CONTRACT

The contract with the successful Respondent shall substantially be in the form attached to or provided with this Request for Quotation and identified as ESC2026-011-Q - Contract - Minor Works.

PART 5 – SCOPE

The Scope is as follows:

50 meters (excluding the existing gate to remain) of fencing has been destroyed in the 2025 DRFA event (see image below). Located past the golf club on St George Street, Georgetown, Queensland, 4871.

This projects scope is to;

1. Demolish and remove existing damaged fencing.
2. Reinstatement of surface within the construction area.
3. The supply, delivery and installation of fencing at the entrance of the Georgetown Cemetery (including all connections to existing fencing and gates).

The fence is to be reinstated to its original condition, including suitable connection to other existing fences and gates. The previous installation consisted of 1200 mm-high loop-top aluminium panels, powder coated finish, pearl white. Refer to the ESC2026-011-Q- Contract - Minor Works, annexure part C for the scope of works sketch.

The fencing quotation shall include, but not be limited to, the following components:

- Loop-top aluminium fence panels: 1200 mm (H) × 2475 mm (W) (19mm round aluminium loop top vertical through rails).
- Aluminium posts: 50 × 50 × 1.8 mm SHS.
- Post caps: 50 × 50 mm flat black plastic caps.
- Rail brackets: 38 × 25 mm.
- Fixings: 3/8 × 22 mm steel teks, white finish.

Image of the current Georgetown Cemetery Fencing state



PART 6 – RESPONSE SCHEDULES

The Quotation must be submitted in the form provided in the Response Schedules attached to or provided with this Request for Quotation and identified as ESC2026-011-Q - Response Schedule.